|         |   | MODI   | EL DATA - FOR CO   | MPRESSED AIR   |                                |                         |
|---------|---|--|--|--|--------------------------------|-------------------------|
|         | 1   | Manufacturer:  | Atlas Copco  |  |                                |                         |
|         |   | Model Number: <b>ZR 275 - 150</b>  |  | Date:  | 01-09-2019                     |                         |
|         | 2   | Air-cooled   | X Water-cooled   | Type:  | Screw                          | _                       |
|         |   | Oil-injected   | X Oil-free   | # of Stages:   | 2                              |                         |
|         |   | Rated Capacity at Full Load Operating  |  |  |                                |                         |
|         | 3*  | Pressure <sup>a, e</sup>   |  | 1356.0   | acfm <sup>a,e</sup>            |                         |
|         | 4 Full Load Operating Pressure <sup>b</sup>   |  | Pressure <sup>b</sup>  | 151  | b                              | -                       |
|         | 5   | 5 Maximum Full Flow Operating Pressure <sup>c</sup>  |  | 151  | psig <sup>c</sup>              |                         |
|         | 6   | Drive MotorNominal   | Rating   | 349  | hp                             |                         |
|         | 7   | 7 Drive Motor Nominal Efficiency   |  | 96.2   | percent                        |                         |
|         | 8   | Fan Motor Nominal Rating (if applicable)   |  | -  | hp                             | _                       |
|         | 9   | Fan Motor Nominal Efficiency   |  | -  | percent                        | _                       |
|         | 10*   | Total Package Input I  | Power at Zero Flow <sup>e</sup>  | 46.0   | kW <sup>e</sup>                | _                       |
|         | 11  | Total Package Input Power at Rated Capacity<br>and Full Load Operating Pressure <sup>d</sup> |  | 273.2  | $kW^d$                         |                         |
|         | 12*   |  | ad Operating Pressure <sup>e</sup>   | 20.1   | kW/100 cfm <sup>e</sup>        |                         |
|         | *For models that are tested in the CAGI Performance Verification Program, these items are verified by the third party admi<br>Consult CAGI websitefor a list of participants in the third party verification program: <u>www.cagi.org</u> |  |  |  |                                | lministrator.           |
|         | NOTES:  | _  | harge terminal point of the com  |  |                                |                         |
|         |   | b. The operating pressu  | ACFM is actual cubic feet per r<br>re at which the Capacity (Item 3  |  | (Item 11) were measured        |                         |
| pressed | Member<br>Air & Gas Institute   | maximum pressure a<br>d. Total package input   | ttainable at full flow, usually the<br>ttainable before capacity control<br>power at other than reported ope<br>d in ISO 1217, Annex C, as sho | begins. May require addition<br>trating points will vary with co | nal power.                     |                         |
|         |   | Volume Flow Rate<br>at specified condition   |  | Volume Flow Rate   | Specific Energy<br>Consumption | No Load / Zero<br>Power |
|         |   | <u>m<sup>3</sup> / min</u>   | <u>ft3 / min</u>   | %  | %                              |                         |
|         |   | Below 0.5  | Below 15   | +/- 7  | +/- 8                          |                         |
|         |   | 0.5 to 1.5   | 15 to 50   | +/- 6  | +/- 7                          | +/- 10%                 |
|         |   | 1.5 to 15  | 50 to 500  | +/- 5  | +/- 6                          |                         |
| 030     |   | Above 15   | Above 500  | +/- 4  | +/- 5                          |                         |