

## **COMPRESSOR DATA SHEET**

## In Accordance with Federal Uniform Test Method for Certain Lubricated Air Compressors Rotary Compressor: Dual Speed

| MODEL DATA - FOR COMPRESSED AIR (Preliminary Data) |  |                                    |              |                         |  |  |
|--|--|------------------------------------|--------------|-------------------------|--|--|
| 1  | Manufacturer:  | Atlas Copco                        |              |                         |  |  |
|  | Model Number:  | GA11 FLX                           | Date:        | 3/18/2024               |  |  |
| 2  | X Air-cooled   | <b>0</b> Water-cooled              | Type:        | Screw                   |  |  |
|  |  |                                    | # of Stages: | 1                       |  |  |
| 3*   | Rated Capacity at Full Load (  | Operating Pressure <sup>a, e</sup> | 58.6         | acfm <sup>a,e</sup>     |  |  |
| 4  | Full Load Operating Pressure   | b                                  | 175          | psig                    |  |  |
| 5  | Maximum Full Flow Operatin   | ng Pressure <sup>c</sup>           | 181          | psig <sup>c</sup>       |  |  |
| 6  | Drive Motor Nominal Rating   | brive Motor Nominal Rating 15      |              | hp                      |  |  |
| 7  | Drive Motor Nominal Efficie  | ncy                                | 94.6         | percent                 |  |  |
| 8  | Fan Motor Nominal Rating (i  | f applicable)                      | NA           | hp                      |  |  |
| 9  | Fan Motor Nominal Efficienc  | у                                  | 80.0         | percent                 |  |  |
| 10*  | Total Package Input Power at   | Zero Flow <sup>e</sup>             | 1.8          | kW <sup>e</sup>         |  |  |
| 11   | Total Package Input Power at<br>Load Operating Pressure <sup>d</sup> | Rated Capacity and Full            | 14.7         | $kW^d$                  |  |  |
| 12*  | Specific Package Input Power<br>Full Load Operating Pressure         |                                    | 25.1         | kW/100 cfm <sup>e</sup> |  |  |
| 13   | Isentropic Efficiency  |                                    | 71.37        | Percent                 |  |  |

\*For models that are tested in the CAGI Performance Verification Program, these items are verified by the third party administrator. Consult CAGI websitefor a list of participants in the third party verification program: www.cagi.org

NOTES:

a. Measured at the discharge terminal point of the compressor package in accordance with ISO 1217, Annex C; ACFM is actual cubic feet per minute at inlet conditions.





- b. The operating pressure at which the Capacity (Item 3) and Electrical Consumption (Item 11) were measured for this data sheet.
  c. Maximum pressure attainable at full flow, usually the unload pressure setting for load/no load control or the
- c. Maximum pressure attainable at full flow, usually the unload pressure setting for load/no load control or the maximum pressure attainable before capacity control begins. May require additional power.
- d. Total package input power at other than reported operating points will vary with control strategy.e. Tolerance is specified in ISO 1217, Annex C, as shown in table below:
  - NOTE: The terms "power" and "energy" are synonymous for purposes of this document.

| Volume Flow Rate<br>at specified conditions |  |  | Consumption  | Flow Power   |
|---|--|--|--|--|
| $\underline{m^3 / \min}$                    | <u>ft3 / min</u>   | %  | %  |  |
| Below 0.5                                   | Below 17.6   | +/- 7  | +/- 8  |  |
| 0.5 to 1.5                                  | 17.6 to 53   | +/- 6  | +/- 7  | +/- 10%  |
| 1.5 to 15                                   | 53 to 529.7  | +/- 5  | +/- 6  |  |
| Above 15                                    | Above 529.7  | +/- 4  | +/- 5  |  |
| ]   | <u>m<sup>3</sup> / min</u><br>Below 0.5<br>0.5 to 1.5<br>1.5 to 15 | $m^3 / min$ $ft3 / min$ Below 0.5         Below 17.6           0.5 to 1.5         17.6 to 53           1.5 to 15         53 to 529.7 | $m^3 / min$ $ft3 / min$ %           Below 0.5         Below 17.6         +/- 7           0.5 to 1.5         17.6 to 53         +/- 6           1.5 to 15         53 to 529.7         +/- 5 | $\underline{m^3 / \min}$ $\underline{ft3 / \min}$ %         %           Below 0.5         Below 17.6         +/- 7         +/- 8           0.5 to 1.5         17.6 to 53         +/- 6         +/- 7           1.5 to 15         53 to 529.7         +/- 5         +/- 6 |